

**1.0 DRAWING NOTES:**

- Contractor to verify and locate all underground and above ground utilities. All infrastructure conflicts shall be reported immediately to site engineer.
- Test pit details are provided in the Geotechnical Report prepared by Pinchin dated May 2, 2022.
- All dimensions are in meters or millimeters unless otherwise specified.
- See details for all curb and sidewalk works.
- All concrete shall be Normal Portland Cement. Minimum strength required is 30 Mpa at 28 days.
- Proposed elevations are approximate. Modifications to proposed elevations are to be approved by the site engineer.
- Install light duty silt fence, straw bales and all erosion control measures prior to construction start. Straw bale check dam installation as per OPSPD 219.180. Light duty sediment fence installation as per OPSPD 219.110.
- All construction debris are to be kept on site unless otherwise disposed with direction of Site Engineer.
- Contractor is responsible for cleaning and all costs associated with construction debris on city and site roadways.
- Contractor shall reinstate all disturbed existing areas at the contractor's expense.
- All public within 120m radius shall be notified 48 hours prior to any blasting operations (if required).
- Heavy Duty Pavement and Gravel Structure:
  - HEAVY DUTY GRAVEL STRUCTURE**
    - 300mm Gran A, Compacted 100% SPMDD
    - 600mm Granular B Type II, Compacted to 100% SPMDD
  - HEAVY DUTY PAVEMENT STRUCTURE**
    - 50mm HL1 or Superpave 12.5 FC1 Surface Course SS-1 Tack Coat
    - 80mm HD8C or Superpave 19.0 Binder Course
    - 300mm Gran A, Compacted 100% SPMDD
    - 600mm Granular B Type II, Compacted to 100% SPMDD
- Sodding of ditch side slopes installation as per OPSPD 218.010.
- If paved, accessible parking space shall be marked by an identifying marker on the pavement consisting of the international symbol of access as a 1.53x1.53m white border and symbol with a blue background field colour centered on the parking stall 0.5-0.8m from the traffic aisle. All accessible parking spaces shall be appropriately signed in accordance with provincial regulations.
- See electrical drawings for utilities services details.
- The site Survey has been completed by Hopkins Chitty Land Surveyors Inc. dated Dec 10, 2021.
- Grades are to match adjacent property grades unless otherwise noted.
- Contractor to submit, for review, a testing, disinfection and final connection plan completed by a professional engineer, prior to testing and disinfection of the watermain and large services.
- Site servicing to be inspected by the Building Department.

- WATER**
  - Proposed well locating to be drilled by qualified contractor.
  - Contractor shall provide minimum 1.7m cover over watermain at all locations. Water services shall be Type K copper and shall be installed as per OPSPD 1104.20.
  - Watermain fittings and thrust blocks to be installed as per OPSPD 1103.01 and 1103.02.
  - Watermain tracer wire and cathodic protection to be installed as per City of Kingston standards.
  - No water service joints can be in place from the property line to the building.
  - All mains and services shall be marked with a 50mm wide detectable metallic tape blue in colour with the wording "Buried Water Line Below". The tape shall be SETON PRODUCT #48302 or equivalent. The tape shall be laid 300 to 450mm above the main or service.
  - Approved water service boxes for 38mm & 50mm diameter services. Must be Cat. No. A-753 or equal complete with cast iron centre brass nut, 1200mm stainless steel rod and stainless steel cotter pins.

- ENVIRONMENTAL**
  - While undertaking clearing, demolition, excavation or construction the Owner and their contractors shall be vigilant for the potential presence of underground fuel tanks, contaminated soil or groundwater, buried wastes, designated substances or abandoned water wells. If any of the above are encountered or suspected, the Owner shall ensure that:
    - The Leeds and The Thousand Islands is advised that contaminants or wastes have been discovered or are suspected;
    - Any soil or groundwater contamination encountered is to be managed in accordance with all applicable regulations and standards;
    - Any wastes generated by site clean-ups are managed in accordance with applicable laws and standards;
    - Any abandoned fuel tanks encountered are decommissioned in accordance with applicable laws and standards;
    - Any unused water wells (drilled or dug) are properly abandoned in accordance with Ontario Regulation 903 - Wells or as revised;
    - If it appears likely that contamination, including the presence of designated substances, extends beyond the boundaries of the subject property, the Owner notifies the local office of the Ministry of the Environment and the Leeds and The Thousand Islands;
    - Construction wastes are not to be buried within the property that is the subject of this Agreement; and
    - 3.8. That the Owner and their contractors report all spills to the Ministry of the Environment's Spill Action Centre (1-800-268-6060) and to the Municipality (546-4291 ext. 1368) forthwith.

- GEOTECHNICAL**
  - A qualified geotechnical engineer should be on-site:
    - During the foundation preparation to ensure the subsurface conditions are the same/similar to what was observed during the investigation.
    - To observe placement operations and perform field density tests at random locations throughout each lift, to indicate the specified compaction is being achieved.
    - During the proof roll and foundation preparation activities to verify the recommended level of compaction is achieved and to verify the design assumptions and recommendations.
  - The existing organics are not considered suitable to remain below the proposed building, access roadway and parking areas and will need to be removed.
  - Structural fill must extend at least 1 m beyond the edges of proposed foundations, and then outward and downwards to competent soil at 1 horizontal to 1 vertical. Prior to placing any fill material at the Site, the subgrade should be inspected by a qualified geotechnical engineer and loosened/soft pockets should be sub excavated and replaced with engineered fill.
  - It is recommended that any fill required to raise grades below the proposed building comprise imported Ontario Provincial Standards and Specifications (OPSS) 1010 Granular B Type I or II material.
  - An initial thicker lift of bone sand and gravel may be needed for stability where the groundwater table is near the subgrade level.
  - Where workers must enter trench excavations deeper than 1.2 m, the



- trench excavations should be suitably sloped and/or braced in accordance with the Occupational Health and Safety Act (OHS), Ontario Regulation 213/91, Construction Projects, July 1, 2011, Part III - Excavations, Section 226.
- Prior to commencing excavations, it is critical that all existing surface water and potential surface water is controlled and diverted away from the Site to prevent infiltration and subgrade softening. At no time should excavations be left open for a period of time that will expose them to precipitation and cause subgrade softening. At no time should excavations be left open for a period of time that will expose them to precipitation and cause subgrade softening.
- All collected water is to discharge a sufficient distance away from the excavation to prevent re-entry. Sediment control measures, such as a silt fence, should be installed at the discharge point of the dewatering system.
- Material must be compacted to a minimum of 100% Standard Proctor Maximum Dry Density (SPMDD) prior to installing the concrete formwork. Any soft/loose areas which are not able to achieve the recommended 100% SPMDD are to be removed and replaced with a similar soil type.
- Qualified geotechnical engineering consultant should be on-site during the proof roll and foundation preparation activities to verify the recommended level of compaction is achieved and to verify the design assumptions and recommendations.
- As well, it could be easily disturbed if travelled on during construction. Once it becomes disturbed it is no longer considered adequate to support the recommended design bearing pressures. It is recommended that a working slab of lean concrete (mud slab) be placed in the footing areas immediately after excavation and inspection to protect the founding soils during placement of formwork and reinforcing steel.
- Prior to commencing excavations, it is critical that all existing surface water, potential surface water and perched groundwater are controlled and diverted away from the work Site to prevent infiltration and subgrade softening. At no time should excavations be left open for a period of time that will expose them to inclement weather conditions and cause subgrade softening.
- The subgrade should be sloped to a sump outside the excavation to promote surface drainage and the collected water pumped out of the excavation. Any potential precipitation or seepage entering the excavations should be pumped away immediately (not allowed to pond).
- The footing areas should be cleaned of all deleterious materials such as organics, fill, disturbed or caved materials; and
- If the excavated subgrade soil remains open to weather conditions and groundwater seepage, sidewall stability and suitability of the subgrade soil will need to be verified prior to construction.
- It is recommended the following transition precautions to mitigate/accommodate potential differential settlements: for strip footings, the transition zones should be adequately reinforced steel lap lengths or widened footings; steel reinforced poured concrete foundation walls; and control joints throughout the transition zone(s).
- Where strip footings are founded at different elevations, the subgrade soil is to have a maximum slope of H to 1 V, with the concrete footing having a maximum rise of 600 mm and a minimum run of 600 mm.
- Perimeter foundation drains in order to eliminate the potential for water pooling up within the foundation wall backfill. The foundation drains should consist of a minimum 150 mm diameter fabric wrapped perforated drainage tie surrounded by 19 mm diameter clear stone with a minimum cover of 150 mm on top and sides and 50 mm below the drainage tie
- Clear stone gravel should be wrapped in a non woven geotextile (Terrafix 270R or equivalent)
- The perimeter foundation backfill should consist of a free draining granular material, such as a Granular B Type I (OPSS 1010) or an approved sand fill, extending a minimum lateral distance of 600 mm beyond the foundation.
- All granular material is to be placed in maximum 300 mm thick lifts compacted to a minimum of 100% SPMDD on the interior of walls and below hard landscaping areas and 95% SPMDD in soft landscaping areas.
- Establish the concrete floor slab on a minimum 300 mm thick layer of Granular A, (OPSS 1010) compacted to at least 100% SPMDD. Any required upfill should consist of an OPSS 1010 Granular B, Type I or Type II material.
- The installation of a vapour barrier may be required under the floor slab. If required, the vapour barrier should conform to the flooring manufacturers and designer's requirements. Consideration may be given to carrying out moisture emission and/or relative humidity testing of the slab to determine the concrete condition prior to flooring installation. To minimize the potential for excess moisture in the floor slab, a concrete mixture with a low water-to-cement ratio (i.e., 0.5 to 0.55) should be used.
- Fill material is required to increase the grade to the underside of the gravel surfaced structure it should consist of an OPSS 1010 Granular B, Type I or II material. The up-fill material is to be placed in maximum 300 mm thick lifts compacted to 98% SPMDD within 4% of the optimum moisture content.
- Confirmed that all geotechnical aspects of the project be reviewed and confirmed under the appropriate geotechnical supervision, to routinely check such items. This includes but is not limited to inspection and confirmation of the undisturbed natural subgrade material prior to subgrade preparation, pouring any foundations or footings, backfilling, or engineered fill installation.

479 Hwy 2, Leeds and The Thousand Islands	Zone Review No. 09-076	CURRENT ZONING (Rural (R) (Other Uses))	PROPOSED	REQUIRED Special Rural (SR) (Rural Industrial (RI))	REQUIRED Rural Industrial (RI)	REQUIRED
Permitted Use			Tree Care Service	Contractors Shop/Yard	Contractors Shop/Yard	No
Lot Area (min)	6000m <sup>2</sup>		22.6 Ha	1.0 Ha	60.0m	No
Lot Frontage	46.0m		174.0m			No
Hard Encroachment	No					No
Front	7.5m		83.7m	12.0m		No
Side	10.5m		443.5m	12.0m		No
Rear	7.5m		12.0m	12.0m		No
Building Height (max)	12.0m		9.3m	15.0m		No
Watercourse Setback	30m		30m	20%		No
Provincially Significant Wetland	226m		285.5m			No

Area Coverage	Area (Ha)	%
Asphalt/Gravel	0.569	2.52%
Building/Coverall	0.116	0.51%
Landscaping	21.915	96.97%
Total	22.6	100.00%

Building Stats	Value
Ground Floor Area	563.27m <sup>2</sup>
Gross Floor Area	753.45m <sup>2</sup>
Height of Building	9.3m
Number of Stories	2

- DISCLAIMER**
  - Any unforeseen infrastructure will be dealt with during construction stages.



**ECO TREE CARE**  
 479 HWY 2,  
 GANANOQUE, ON

CLIENT:  
**JOHN MADDEN**

**ASTERISK**  
 ENGINEERING CORPORATION  
 1480 Bath Road  
 Kingston, ON.  
 K7M 0X6  
 (613) 542-2040 fax 1 613 280-1335  
 www.asteriskengineering.com

ISSUED FOR	REV	DATE
SPC	00	MAY 16, 2022

Do not scale drawings. Refer to Architectural drawings for dimensions. All elevations/dimensions shall be verified with Architectural drawings and any discrepancy shall be reported immediately to consultant. Read this drawing in conjunction with ALL applicable Architectural, Mechanical, electrical and other disciplines involved. This drawings are "design drawings" only and are not intended to be used as shop drawings.

**LEGEND**

- Proposed Down Spout
- Heavy Duty Gravel Surface
- Proposed Septic
- Proposed Coverall (Phase II)
- Proposed Fire Route
- Proposed Swale/Ditch
- Proposed Swale/Ditch Centerline
- Building Envelop
- Bore Hole Location and ID
- Silt Fence
- Straw Fence
- Rock Check Dam
- Phase II Boundary

Professional Engineer Seal: T. AMARAL/REG. NO. 10007414, May 16, 2022, PROVINCE OF ONTARIO

SCALE: 1:500 UNITS: m

DESIGNED: TC CHECKED: TC DRAWN: MT/CR

DRAWING TITLE:  
**SITE PLAN**

DRAWING NO.:  
**C-01**

PROJECT NO.: 21-109  
 DATE: MAY 16, 2022

# ECO TREE CARE

479 HWY 2,  
GANANOQUE, ON

CLIENT:  
JOHN MADDEN

**ASTERISK**  
ENGINEERING CORPORATION  
1480 Bath Road  
Kingston, ON  
K7M 0X6  
(613) 542-2040 fax 1 613 280-1335  
www.asteriskengineering.com

ISSUED FOR: SPC  
REV: 00  
DATE: MAY 16, 2022

Do not scale drawings. Refer to Architectural drawings for dimensions. All elevations/dimensions shall be verified with Architectural drawings and any discrepancy shall be reported immediately to consultant. Read this drawing in conjunction with ALL applicable Architectural, Mechanical, electrical and other disciplines involved. This drawings are "design drawings" only and are not intended to be used as shop drawings.

## LEGEND

- Proposed Down Spout
- Proposed Overland Flow Direction
- Proposed Ditch/Swale Flow Direction
- Proposed Grading
- Heavy Duty Gravel Surface
- Proposed Septic
- Proposed Coverall (Phase II)
- Proposed Swale/Ditch
- Proposed Swale/Ditch Centerline
- Proposed Parking Space
- Building Envelop
- Silt Fence
- Straw Fence
- Rock Check Dam
- Tributary Area
- Coefficient


SCALE: 1:500 UNITS: m  
DESIGNED: TC CHECKED: TC DRAWN: MT/CR


DRAWING TITLE:

## SERVICING AND GRADING


DRAWING NO.: C-02

PROJECT NO.: 21-109  
DATE: MAY 16, 2022







(G) TYPICAL SWALE CROSS SECTION




NOTES:  
 1 The thickness of the rip-rap layer shall be at least 1.5 times the rip-rap mean diameter.  
 A All dimensions are in millimetres unless otherwise shown.



(A) DETAILS FOR GRASS STORAGE AREA CROSS SECTION




(D) SECTION OF SWM STORAGE OUTLET



(B) TYPICAL SPILLWAY SECTION

(C) TYPICAL SPILLWAY SECTION



(E) POND OUTLET DETAILS

(F) SECTION F-F

**ECO TREE CARE**  
 479 HWY 2,  
 GANANOQUE, ON


CLIENT:  
**JOHN MADDEN**

**ASTERISK**  
 ENGINEERING CORPORATION  
 1480 Bath Road  
 Kingston, ON.  
 K7M 0X6  
 (613) 542-2040 fax 1 613 280-1335  
 www.asteriskengineering.com


ISSUED FOR	REV	DATE
SPC	00	MAY 16, 2022

Do not scale drawings. Refer to Architectural drawings for dimensions. All elevations/dimensions shall be verified with Architectural drawings and any discrepancy shall be reported immediately to consultant. Read this drawing in conjunction with ALL applicable Architectural, Mechanical, electrical and other disciplines involved. This drawings are "design drawings" only and are not intended to be used as shop drawings.


**LEGEND**



NOTE:  
 A All dimensions are in millimetres unless otherwise shown.



NOTE:  
 A All dimensions are in millimetres unless otherwise shown.



NOTES:  
 1 Number of bales varies and shall suit ditch.  
 2 Straw bales shall be butted tightly against adjoining bales and shaped to conform to the sides of the ditch to prevent water flow through barrier.

A All dimensions are in millimetres unless otherwise shown.



SCALE: -	UNITS: m
DESIGNED: TC	CHECKED: TC DRAWN: MT/CR

DRAWING TITLE:  
**DETAILS**

DRAWING NO.:  
**C-03**

PROJECT NO.: 21-109  
 DATE: MAY 16, 2022